



Contractor Series (CSW) - Wall Pack

- Built-In Photocontrol
- Universal Input 120-277V, 0-10V Dimming
- Selectable Output 25W ~ 120W
- Selectable Lumen 4,000 ~ 16,500LM
- Selectable CCT 3000 / 4000 / 5000K
- EMB (Factory/Field)
- Wet Location Listed



Mounting Bracket

- Wall Mount

